

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01676-00-01
Spot: SWNESW Sec/Twnshp/Rge: 3-10S-21W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MILLER Well #: 5
County: GRAHAM Total Vertical Depth: 1985 feet

Operator License No.: 32705
Op Name: RANEY OIL COMPANY, LLC
Address: 3425 TAM O'SHANTER
LAWRENCE, KS 66047

String	Size	Depth (ft)	Pulled (ft)	Comments
RBP	5.5	3841	0	w/unknown sxs cmt
SURF	8.625	246	0	w/unknown sxs cmt

#64.51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2007 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: IRVIN HASELHORST Company: RANEY OIL COMPANY, LLC Phone: (785) 620-1154

Proposed Plugging Method: Ordered 75 sxs 60/40 pozmix - 4% gel.
Drilled to 1985'. Bad casing at 1565' - unable to get below 1565' - iron in the hole.
Lost hole at 1985' - decided to P/A.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2007 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Hole full of drilling mud.
Ran tubing to 1550'. Allied pumped 15 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1075'. Allied pumped 30 sxs cement.
Pulled to 300'. Allied pumped 15 sxs.
Pulled tubing to 60'. Allied pumped 15 sxs cement.

Perfs:

INVOICED
DATE 9-19-07
INV. NO. 2008060430

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 12 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

SEP 10 2007

ANDERSON-PRICHARD OIL CORP

#5

MILLER

3-10-21W 22
SW NE SW

Contr.

GRAHAM

County

E 2283RB Comm.

Comp.

12-22-50

IP

3000 BOPD

DRAW DOWN

Tops	Depth	Datum
ANH	1752	+ 531
HEEB	3490	- 1207
LANS	3526	- 1349
CONG	3802	- 1519
SIMP	3837	- 1554
ARB	3841	- 1558
T.D.	3844	- 1561

Casing

8" 246 SWB 29 BOPH
5" 3841 ACID 250

Ally 12-1-73

TEALL NE POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS