

4- 090492

8-15

18 R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,207-00-00

NE NE SE /4 SEC. 15, 10 S, 18 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 31003 Lease Valenta well # 1

Operator: Howard S. Shepard County Rooks

Address: 1325 State Street Well total depth 3765 feet <sup>122.36</sup>  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
(913) 625-8160 Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 14 Month: August Year: 92

Plugging proposal received from: Larry Longhofer

Company: Emphasis Oil Operations Phone: -

Were: Spot plugs through drill pipe with heavy mud between all plugs.  
1st. plug @ 1560 feet with 20 sacks.  
2nd. plug @ 940 feet with 100 sacks.  
3rd. plug @ 305 feet with 40 sacks.  
4th. plug @ 40 feet with 10 sacks.  
Rat hole: 15 sacks.  
Mousehole: 10 sacks.

Plugging Proposal Received by: Ed Schumacher - P.I.R.T. III

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:30P.M., Day 15, Month: August, Year: 92

Actual plugging report: Hole reported plugged as above.  
Order 195 sx. 60/40 pozmix with 6% gel. and 2 sx. celloflake or flocele.

Remarks: Cemented by: Allied Cementing Company  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES  NO   
Plugged through TUBING , CASING . Elevation: 2163 GL

I did[  ] / did not[  ] observe the plugging. Ed Schumacher

DATE 9-29-92

INV. NO. 36268

(agent)

Form CP-2/3

STATE CORPORATION COMMISSION  
RECEIVED  
09-24-1992  
SEP 24 1992  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

MD