

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19063-00-0D
Spot: NESWSE Sec/Twnshp/Rge: 3-12S-16W
1024 feet from S Section Line, 1719 feet from E Section Line
Lease Name: DREILING F Well #: 10
County: ELLIS Total Vertical Depth: 3837 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	3360		
PROD	7	3405	0	w/225 sxs cmt
SURF	10.75	165	0	w/100 sxs cmt

\$ 124.70

Well Type: EOR UIC Docket No: E24645.1 Date/Time to Plug: 09/11/2007 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL, INC. Phone: (785) 735-2289

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 800# hulls.
Perf's liner slotted 3650'-3670'; 3800'-3830'.
DV 942' w/500 sxs. Present TD 2912' - casing collapsed.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2007 7:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH to 2883'.
Allied rigged to tubing and pumped 50 sxs 60/40 pozmix - 4% gel w/250# hulls.
Tubing stuck in the hole.
LK Wireline shot off tubing at 2500'.
Express Well Service pulled one joint. Allied rigged to tubing and pumped 15 sxs gel.
Pulled tubing to 1000'. Allied rigged to tubing and pumped 125 sxs cement w/250# hulls to circulate cement to surface.
Pulled tubing - rigged to 7" casing and pumped 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
10 3/4" casing was not dug out at this time.

Perfs:

Top	Bot	Thru	Comments
2730	3329		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 18 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 9/20/07
INV. NO. 2008060447

Remarks: ALLIED CEMENTING COMPANY-TICKET #30879.

Plugged through: TBG

District: 04

PT

Signed

Pat Staab

(TECHNICIAN)

SEP 12 2007

PT

LEO J DREILING #10 DREILING 'F' 3-12-16W
 NE SW SE
 Contr. MAST DRLG ELLIS County
 E 1775RB Comm. 7-4-59 Comp. 8-28-59 IP 97 BOPD
 PHY POT

Tops	Depth	Datum
ANH	937	+838
TOP	2683	-908
HEEB	2945	-1170
LANS	2992	-1217
KC	2994	-1219
SIMP SND	3293	-1518
ARB	3311	-1536
TD	3509	-1734

Casing
 5" 3405
 PERF 3317-23: 10 BOPH

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

