

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-00113-00-00  
Spot: NE Sec/Twnshp/Rge: 34-31S-33W  
1320 feet from N Section Line, 3960 feet from W Section Line  
Lease Name: FAIR B Well #: 1-34  
County: SEWARD Total Vertical Depth: 6200 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2650		\$201.50
CIBP		5830		
PROD	5.5	6020	0	WITH 320 SX CMT
SURF	8.625	722		WITH 600 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/05/2007 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 500LBS COTTON SEED HULLS AND 25 SX SEMENT. PU AND SPOT 50 SX CEMENT PLUG @ 3,000'.  
PERFORATE 4 HOLES @ 625'. SQUEEZE WITH 25 SX OF CEMENT. TIE ONTO 8 5/8" X 5 1/2" ANNULUS AND  
PUMP 50 SX.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/05/2007 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 500# HULLS & 75 SX CMT ON BOTTOM. CIBP @ 2650'. PRESSURED TO 500 PSIG. PERFORATE AT 750'. PUMP 175 SX CMT FROM 750' TO 0' INSIDE 5 1/2" & 8 5/8" ANNULUS. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:


Top	Bot	Thru	Comments
5870	5872		ST. LOUIS
5720	5728		CHESTER
4942	4948		MARMATON/CHE

**INVOICED**  
DATE 9-20-07  
INV. NO. 200 8060441

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Jim Holland PERT-III

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 17 2007

CONSERVATION DIVISION  
WICHITA, KS

Form CP-27