

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20340-00-00
Spot: SE Sec/Twnshp/Rge: 24-21S-34W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: FLEAGLE Well #: 1
County: FINNEY Total Vertical Depth: 2660 feet

Operator License No.: 32581
Op Name: EXCO RESOURCES, INC.
Address: 12377 MERIT DRIVE, STE 1700, ~~LB-82~~
DALLAS, TX 75251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1099		
PROD	4.5	2657	0	WITH 200 SX CMT
SURF	8.625	568		WITH 400 SX CMT

\$ 86.45

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/10/2004 1:00 PM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: BRENT TALICK Company: EXCO RESOURCES Phone: (214) 368-2084

Proposed Plugging Method: TOP OF FISH @ 1300'. CIBP @ 1100' TEST CSG. PERFORATE AT 1050'. PUMP 140 SX CMT DOWN CASING. 140 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2007 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 1099'. TEST CASING TO 600 PSI & HELD. PERFORATE AT 1050'. PUMP 130 SX CMT DOWN 4 1/2" CASING. AFTER 1 HOUR, CMT AT SURFACE. NO BLOW OR CIRCULATION UP 4 1/2" X 8 5/8" ANNULUS. HOOK TO 4 1/2" X 8 5/8" ANNULUS AND PUMP 100 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2556	2572		

INVOICED
DATE 9/20/07
INV. NO. 2008060443

Remarks: USED 60/40 POZMIX 4% GEL BY ACID SERVICES.

Plugged through: CSG

District: 01



Signed

[Handwritten Signature]

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

[Handwritten Signature]