

7-22

6 040932

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-00898-00-00
C E/2E/2NE SEC. 14, T 10 S, R 18 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

_____ feet from S section line

_____ feet from E section line

Operator: Davis Brothers Oil Prod Inc.
Name & Address: One Williams Center
S. 2000
Tulsa, Ok. 74172

Lease Name Finnesy Well # 2
County _____ Rooks 124.61
Well Total Depth 3834 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 165 w/265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Ks.

Company to plug at: Hour: _____ Day: 22 Month: July Year: 19 88

Plugging proposal received from Chuck Arnold

(company name) Davis Brothers (phone) _____

were: 4 1/2" casing set at 3765'. Top perf 3596' - 3629'. Perf anhy at 1500' and base
Dakota at 900' 3 holes each. Tubing fish at 2697'. Ordered 260 sks 65/35 Poz
10% Gel 2% Lite w/1/4# Flocele plus 6 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
09-16-1988
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 22 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 200 sks cement w/1/4# Flocele plus 4 sks Hulls,
mixed in cement. Max 500# S.I. 300# Psi.

Pumped in 8 5/8" casing 60 sks cement w/1/4# Flocele plus 2 sks Hulls mixed in cement.
Max 500#. S.I. 300# Psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did) (did not) observe this plugging.

INVOICED
DATE 9-20-88
INV. NO. 22291

Signed Dennis L. Hamel
(TECHNICIAN)