

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20727-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 30-1S-33W
660 feet from S Section Line, 4400 feet from E Section Line
Lease Name: WOLTERS Well #: 13-30
County: RAWLINS Total Vertical Depth: 4250 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: 408 MAIN ST PO BOX 450
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4258	0	385 SX CMT
SURF	8.625	325	0	200 SX CMT

\$ 138.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2007 2:30 PM
Plug Co. License No.: 3602 Plug Co. Name: PHILPOTT OIL & GAS CO INC
Proposal Rcvd. from: ROGER W PHILPOTT Company: PHILPOTT OIL & GAS CO INC Phone: (785) 626-3011

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2007 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:
8 5/8" surface casing set at 325' w/200 sxs.
4 1/2" production casing set at 4258' w/385 sxs.
TD 4250'. PBD 4245'.
Connected to 4 1/2" production casing - pumped 280 sxs cement with 500# hulls.
Max P.S.I. 165#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 62.5 sxs cement.
Max. P.S.I. 10#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
4178	4181		
4088	4094		
4048	4178		

INVOICED

DATE 9-17-07
INV. NO. 2008060400

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 06 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENT COMPANY-TICKET #104.
Plugged through: CSG

District: 04 Signed Darrel Dipman (TECHNICIAN)

AUG 30 2007

TURNPIKE OIL COMPANY
DENVER, CO 80212

30-01 -33W
110'W, C E/2 SW SW

#13-30 WOLTERS

site: 8-1/4 N & 1-1/4 W OF ATWOOD, KS city: RAWLINS API 15-153-20727
contr: MURFIN DRILLING COMPANY field: VAP SW EXT (1/4 NE)
geol: RIC MORGAN

fr	spd	drig	card	last
date 10/19/88	date 10/21/88	comp 10/26/88	issued 01/04/89	revised 01/04/89

ELV: 3044 KB LOG	IP status:
tops.....depth/datum	OIL, P 29 BO & 66 BWP, LKC 4048-4181 OA,
ANH.....2884 +160	LTD.....4264 -1220
B/ANH.....2921 +123	CSG: 8-5/8" 325 / 200 SX, 4-1/2" 4258 / 385 SX
TOP.....3814 -770	NO CORES
DR CR.....3845 -801	DST (1) 4008-4054 (LANS B), / 30-30-30-60, 180' GIP,
OREAD.....3921 -877	REC 50' MCO (50% OIL, 50% M), 180' MCO (75% OIL,
LANS A.....3992 -948	25% M), 360' GSY OIL (GR 22), 60' M & WCO (75% OIL,
LANS B.....4042 -998	10% M, 15% W), 60' OCMW (65% OIL, 5% M, 30% W)
LANS C.....4088 -1044	ISIP 1164# FSIP 1183# IFP 95# -162# FFP 200# -286#
LANS D.....4135 -1091	IHP 2094# FHP 2084#
LANS E.....4178 -1134	DST (2) 4048-4102 (LANS C), / 30-30-30-60, 300' GIP,
LANS F.....4218 -1174	REC 450' GSY OIL (GR 28), 60' WCO (65% OIL, 35% W),
PBTD.....4245 -1201	210' W ISIP 1193# FSIP 1193# IFP 95# -171# FFP
RTD.....4260 -1216	219# -286# IHP 2123# FHP 2103#

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

TURNPIKE OIL COMPANY
DENVER, CO 80212

30-01 -33W
110'W, C E/2 SW SW

#13-30 WOLTERS

DST (3) 4117-4140 (LANS D), / 30-30-30-60, REC 1' CLEAN OIL, 115' MW, 120' W ISIP 1193#
FSIP 1212# IFP 38# -75# FFP 95# -114# IHP 2180# FHP 2161#
DST (4) 4150-4190 (LANS E), / 30-60-30-60, REC 25' HO SPTD M, 40' MCO ISIP 992# FSIP
858# IFP 38# -38# FFP 47# -47# IHP 2209# FHP 2190#
MICT - CO, PF (LANS E) 4178-4181, W / 4 SPF, AC 600 GAL (NE), SWB LD, RE-AC 1000 GAL
(CRA), SO, PF (LANS C) 4089-4094, W / 4 SPF, AC 500 GAL (MCA), SWB LD, RE-AC 1500 GAL
(NE), SO, RE-PF (LANS C) 4088.5-4093.5, W / 4 SPF, SO, NAT, PF (LANS B) 4048-4051, W / 4
SPF, AC 3000 GAL (MCA), SWB LD, RE-AC 1000 GAL (REG), SO, SET 2-3/8" TBG AT 4194, NO
PKR, POP, P 29 BO & 66 BWP (GR 26.5), 12/1/88