

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21674-00-00
Spot: E2W2W2 Sec/Twnshp/Rge: 16-13S-31W
2500 feet from S Section Line, 1150 feet from W Section Line
Lease Name: PHELPS 16BC Well #: 1
County: GOVE Total Vertical Depth: 4730 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		

\$ 153.73

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/01/2007 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 09/01/2007 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:
1st. Plug at 2475' w/25 sxs.
2nd. Plug at 1518' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:
INVOICED
DATE 9-17-07
INV. NO 2008060402

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 06 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

SEP 04 2007