

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

*Rec'd
06-01-59*

15-163-00918-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 5 Twp. 10S Rge. 18 (E) W (W)

Location as "NE/CNW/4SW/4" or footage from lines Cen. NW/4 SE/4

Lease Owner Rex & Morris, & Osage Oil & Gas Co., Inc.

Lease Name Williams Well No. 1

Office Address Box 334, El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 8 19 59

Application for plugging filed " 19 "

Application for plugging approved " 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 3828 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	219	8 5/8"	219	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud from 3828 to 600': Set bridge plug at 600' and cemented with 20 sacks cement: Filled with mud to 180': Set plug and cemented with 15 Sacks cement: Filled with mud to 40': Set bridge and cemented with 10 Sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure
Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1959

My commission expires August 8, 1962

Elizabeth Deschner Notary Public.

PLUGGING
FILE SEC. 5 T 10 R 18 W
BOOK PAGE 42 LINE 12

Elevation 2191 R.B.
2188 D.F.

15-163-00918-00-00

WILLIAMS #1

Osage Oil & Gas Company, Inc.
and
Rex & Morris Drilling Company

Total Depth: 3828'
Contractor: Rex & Morris Drilling Co.
Commenced: 5-1-59
Completed: 5-8-59
Initial Production: D. & A.

Location: C. NW/4 SE/4
Section 5-10S-18W
Rooks County, Kansas

Casing Record:
8 5/8 @ 219' w/150 sacks

FORMATION	DEPTH
Surface Hole	219
Shale and Sand	1300
Shale and Red Beds	1578
Anhydrite	1618
Shale and Shells	1770
Shale and Lime	2190
Lime and Shale	3045
Shale and Lime	3093
Lime and Shale	3210
Lime	3386
Lime and Shale	3420
Lime	3665
Lime and Shale	3668
Conglomerate	3741
Dolomite	3752
Shale and Lime	3787
Lime (Arbuckle)	3828

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

Paul D. Koontz

Paul D. Koontz, Geologist

STATE OF KANSAS
BUTLER COUNTY, SS.

Subscribed and sworn to before me, a Notary Public, this 20th day of May, 1959.

Elizabeth Deschner
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.

PLUGGING
FILE SEC. 5 T. 10 R. 18W
BOOK PAGE 42 LINE 12