


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-163-00673-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 5 Twp. 10S Rge. _____ (E) 18 (W) _____
Location as "NE/CNW/SW" or footage from lines SE 1/4 SE 1/4 SE 1/4
Lease Owner Barnett Oil Company
Lease Name Williams Well No. 1
Office Address 417 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 2, 19 54
Application for plugging filed April 2, 19 54
Application for plugging approved April 2, 19 54
Plugging commenced April 2, 19 54
Plugging completed April 2, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3767 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	162'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3767 feet to 155 feet. Set wooden plug at 155 feet and filled surface casing with 15 sacks of cement and 1 sack of hulls to 108 feet. Filled surface casing with heavy mud from 108 feet to 40 feet. Set wooden plug at 40 feet and filled surface casing with 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 623 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 54

My commission expires February 27, 1956.
Mildred F. Willis Notary Public.

24-7368-S 3-53-20M

PLUGGING
FILE NO. 5 10 18w
BOOK 24 PAGE 43

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1954
CONSERVATION DIVISION
Wichita, Kansas


15-163-00673-00-00

BARNETT OIL COMPANY
LOG OF WILLIAMS WELL NO. 1
SE¹/₄ SE¹/₄ SE¹/₄, SECTION 5-10S-18W
ROOKS COUNTY, KANSAS

DATE COMMENCED: March 19, 1954

DATE COMPLETED: April 2, 1954

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	
Post Rock	20	30	
Sand	30	70	
Shale	70	90	
River Sand	90	130	
Blue Shale	130	162	Set 8 5/8", 21# surface pipe at 162'; cemented with 125 sacks of cement.
Shale	162	315	
Shale and Shells	315	1015	
Lime	1015	1050	
Shale	1050	1120	
Sand	1120	1230	
Shale and Shells	1230	1590	
Anhydrite	1590	1625	
Shale and Shells	1625	2175	
Shale and Lime Shells	2175	2285	
Shale and Lime	2285	2470	
Lime	2470	2550	
Shale and Lime	2550	2765	
Lime	2765	2875	
Lime and Shale	2875	3240	
Lime	3240	3640	
Lime and Shale	3640	3685	
Lime	3685	3767	
Total Depth		3767	Dry and Abandoned.



RECEIVED
STATE CORPORATION COMMISSION
APR 26 1954
04-26-1954
CONSERVATION DIVISION
Wichita, Kansas