

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-163-00186-00-00

CC

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 5 Twp. 10 Rge. 18 ~~200X~~ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  SE $\frac{1}{4}$  NE $\frac{1}{4}$   
Lease Owner National Cooperative Refinery Assn. & John Lindas  
Lease Name Hilgers Well No. 1  
Office Address 1316 Union National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed November 18, 19 49  
Application for plugging filed November 18, 19 49  
Application for plugging approved November 18, 19 49  
Plugging commenced November 18, 19 49  
Plugging completed November 18, 19 49  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Pettit - Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3782 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	161'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 160'. Cement plug of 15 sacks cement @ 160'. Filled with heavy mud to 30'. Cement plug of 10 sacks @ 30' and finished filling hole with heavy mud.

REC'D

12-21-1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Fred Moore  
Address P. O. Box 470, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Scott Stuckey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. JOHN LINDAS OIL, INC.

(Signature) BY Scott Stuckey  
1316 Union Natl. Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November 19 49.

Catherine Dancy  
Notary Public.

My commission expires March 25, 1952

22-7377-s 4-49-10M

PLUGGING  
FILE SEC. 5 T. 10 R. 18 W  
BOOK PAGE 45 LINE 36

DRILLING LOG

To: The National Cooperative Refinery Association  
 Union National Bank Building  
 Wichita 2, Kansas

Lease: Hilgers #1

County: Booka  
 Section: 5-108-18W  
 Location: SE/4 SE/4 NE/4

Rotary: Total Depth 3782'  
 Commenced: 11-2-1949 Completed: 11-18-1949  
 Shot or Treated:  
 Casing: 8-5/8" @ 161' -- 5-1/2" None  
 Production: Dry

15-163-00186-00-00

Contractor: L-S-T Drilling Co., Inc.  
 1316 Union National Bank Building  
 Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATION		
0	to	70
		Surface Clay and Soil
70		125 Sand and Shale
125		160 Shale and Shells
160		575 Blue Shale
575		1580 Shale and Shells
1580		1590 Red Bed
1590		1640 Anhydrite Line
1640		1940 Shale and Shells
1940		2000 Salt
2000		2120 Shale, Shells and Lime
2120		2300 Lime
2300		2430 Lime and Shale
2430		2470 Lime
2470		2585 Shale and Lime Shells
2585		2715 Shale and Lime
2715		2765 Lime and Shale
2765		2985 Shale and Lime Shells
2985		3150 Shale and Shells
3150		3370 Lime
3370		3405 Lime Chert
3405		3600 Lime
3600		3612 Lime and Shale
3612		3682 Lime
3682		3702 Lime and Chert
3702		3719 Conglomerate and Chert
3719		3740 Arbuckle Dolomite
3740		3782 T.D. Line

STATE OF KANSAS }  
 ) SS:  
 COUNTY OF SEDGWICK }

I, the undersigned, being duly sworn on oath, state that the above statement and log is true and correct record and log of the well drilled at the location above described.

L-S-T DRILLING CO., INC.

By Scott Stucky

Subscribed and sworn to before me this 20th day of November, 1949

Catherine Quincy  
 Notary Public

My commission expires March 25, 1952

**PLUGGING**  
 FILE SEC 5 T 10 R 18 W  
 BOOK PAGE 125 LINE 36

11-17-1949  
 DEC 17 1949  
 STATE OF KANSAS  
 COUNTY OF BOOKA  
 KANSAS