

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00750-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS

County. Sec. 5 Twp. 10 Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines SW/4 NW/4 SW/4

Lease Owner Davis Bros.

Lease Name Davis, rothers- Gilbert Well No. 1

Office Address 14 East Third St., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced Aug. 11 19 58

Plugging completed Aug 14 19 58

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3829 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3829 feet to Surface feet for each plug set.

Hole filled with sand from 3829 to 3590 Ft. (Pipe set at 3817 with top reformation at 3600 to 3610) Three sacks of cement placed at 3590 with dump bailer. Pipe pulled to 550 ft, and Halliburton circulated with mud 30 sacks of mud, followed by twenty sacks of cement; rope then pulled to 180 ft, and Halliburton pump trucks pumped down 20 sacks of cement, and balance of pipe pulled; hole baled down to 35 ft; Ten foot rock bridge installed between 35 and 25 ft and hole capped with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,

Address Russell, Kansas.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Ralph A. Hockenson

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph A. Hockenson

14-East 3rd St. Tulsa - Okla

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 58

Burns Dean

My commission expires 10-1-761

Notary Public.

PLUGGING
FILE SEC 5 T 10 R 18W
BOOK PAGE 120 LINE 44

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1958
09-12-1958

15-163-00750-00-00

DRILLER'S WELL LOG

Transit Corporation - Gilbert # 1 located SW NW SW
Sec. 5-106-18W, Rocks County, Kansas

Commenced: April 28, 1958
Completed: May 11, 1958
Elevation: 2199 KB

Casing 8 5/8" @ 180'
Cemented 135 sacks

Formation	From	To
Surface Clay	0	50
Shale and shells	50	100
Sand	100	160
Shale	160	390
Shale and shells	390	850
Sand	850	1044
Shale and shells	1044	1605
Anhydrite	1605	1640
Shale and shells	1640	2080
Shale and shells w/lime streaks	2080	2185
Lime and shale	2185	2525
Shale w/lime streaks	2525	2570
Shale	2570	2673
Shale and lime	2673	2997
Lime and shale	2997	3052
Lime and shale streaks	3052	3109
Shale w/lime streaks	3109	3175
Lime and shale	3175	3446
Lime and shale streaks	3446	3535
Lime and shale	3535	3581
Lime and shale streaks	3581	3630
Lime and shale	3630	3685
Cherty Conglomerate	3685	3771
Simpson	3771	3780
Simpson Dolomite	3780	3806
Simpson, Dolomite and Artuckle	3806	3827 TD

Summary of Formation

Topeka	3171'
Heekin	3389'
Toronto	3410'
Douglas	3422'
Lansing	3432'
Base Kansas City	3660'
Conglomerate	3683'
Shale Conglomerate	3760'
Simpson	3766'
Artuckle	3806'
Rotary TD	3827'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.


TRANSIT CORPORATION

By *Paul E. Gathers*
Paul E. Gathers

Subscribed and sworn to before me
this 20th day of June, 1958.

My commission expires May 17 1962

Mildred Iron
Notary Public



DIVISION