

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23444-00-00  
Spot: SENWNENE Sec/Twnshp/Rge: 20-12S-15W  
530 feet from N Section Line, 700 feet from E Section Line  
Lease Name: DRISCOLL Well #: 4  
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3307	0	w/unknown sxs cmt
SURF	8.625	223	0	w/unknown sxs cmt <b>\$108.88</b>

Well Type: OX DH KCC PKT 9/17/07 UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2007 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID FUNK Company: GLM COMPANY Phone: (785) 483-1307

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2007 4:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2880' and dumped 5 sxs cement.  
Cut off casing at 2000'.  
Pulled to 1550' - pumped 125 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled to 875' - pumped 40 sxs cement with 100# hulls.  
Pulled to 250' - circulated with 75 sxs cement.

Perfs:

**INVOICED**  
DATE 9-18-07  
INV. NO. 2008060410

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 10 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed *Case Morris*  
(TECHNICIAN)

SEP 05 2007

*PPT*