


15-163-00758-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 10 Twp. 10S Rge. 18W (W) _____
Location as "NE/CNW/SE/SW" or footage from lines NE 1/4 NE 1/4 NE 1/4
Lease Owner Davis Bros.
Lease Name Jones Well No. 1
Office Address 14 East 3rd St., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-13-58 19
Application for plugging filed 5-13-58 19
Application for plugging approved 5-13-58 19
Plugging commenced 5-13-58 19
Plugging completed 5-13-58 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3795 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	192.18	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 500' w/20 sacks cement
2nd plug @ 180' w/15 sacks cement
Top plug @ 40' w/10 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 19 58

My commission expires June 17, 1958

Ruth N. Benjamin
Ruth N. Benjamin
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1958
05-27-1958
CONSERVATION DIVISION
WICHITA, KANSAS
PLUGGING STATE CORPORATION COMMISSION
10 T. 10 18W
PAGE 101 LINE 32

15-163-00758-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

DAVIS BROS.
LEBEN DRILLING, INC.
JONES #1
NE $\frac{1}{2}$ NE $\frac{1}{2}$ NE $\frac{1}{2}$ SEC. 10-10S-10W
ROCKS COUNTY, KANSAS
APRIL 29, 1958
MAY 13, 1958

COMMENCED:
COMPLETED:

0	30	Surface Sand		
30	90	Sand & Shale		
90	192	Blue shale	TOPS:	
192	420	Shale	Anhydrite	1492
420	610	Shale	Topoka	3132
610	715	Shale & Sand	Neobner	3350
715	1010	Shale	Toronto	3370
1010	1215	Sand	Lansing-K.C.	3294
1215	1492	Redbed & shale	Base K.C.	3626
1492	1532	Anhydrite	Harston Line	3032
1532	1805	Shale & Shells	Harston Chert	3644
1805	2630	Lime & Shale	Cherry Congl.	3654
2630	2650	Shale	Arbuckle	3764
2650	3120	Shale & Lime		
3120	3410	Lime	Elevation	2151 K.B.
3410	3545	Lime		
3545	3635	Lime		
3635	3764	Lime		
3764	3795	Dolomite		
	2722	Notary Total Depth - D & A		

Set 192' of 8 5/8" surface casing with 150 sacks cement, 3 sacks Catl. and 1 sack Gal.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Jones #1, located NE $\frac{1}{2}$ NE $\frac{1}{2}$ NE $\frac{1}{2}$ of Section 10, Township 10 South, Range 10 West, Rocks County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 15th day of May, 1958.

Ruth K. Benjamin
Ruth Benjamin - Notary Public

My commission expires: June 17, 1961

PLUGGING	
FILE	SEC 10 T 10 R 10W
BOOK	PAGE 101 LINE 32

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1958