


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above Section Plat

Rocks _____ County. Sec. 7 Twp. 10S Rge. _____ (E) 18 (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NW
Lease Owner Abercrombie Drilling, Inc.
Lease Name TOWNS Well No. 1
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed July 8, 19 64
Application for plugging filed verbally - July 7, 19 64
Application for plugging approved verbally - July 7, 19 64
Plugging commenced July 8, 19 64
Plugging completed July 8, 19 64
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	191'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 550'
Set 1st plug at 550' w/20 sx cement
Set 2nd plug at 180' w/20 sx cement & 1/4 sk hulls
Set 3rd plug at 35' w/ 10 sx cement & 1/4 sk hulls

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1964

07-15-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, B. Lynn Herrington (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington
801 Union Center, Wichita, Kansas, 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 64

My commission expires June 16, 1967

Leah Faye Hefke
Leah Faye Hefke Notary Public.

15-163-02605-00-00

CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 FARM: TOWNS #1
 LOCATION: SW SW NW Sec. 7-10S-18W
 Rooks County, Kansas
 COMMENCED: June 29, 1964
 COMPLETED: July 8, 1964

0	96	Sand
96	730	Shale
730	1240	Shale & Shells
1240	1620	Shale, Shells & Red Bed
1620	1623	Shale
1623	1658	Anhydrite
1658	1990	Shale
1990	3061	Lime & Shale
3061	3135	Lime
3135	3315	Lime & Shale
3315	3665'	Lime
3665		Rotary Total Depth

Set 8-5/8" surface casing at 191' w/135 sx common cement, 2% Calcium Chloride
 DRY AND ABANDONED

ELEVATION: 2195' D. F.
 2189' G. L.

ELECTRIC LOG TOPS:

Anhydrite 1626' (/ 569)
 Topeka 3185' (- 990)
 Heebner 3400' (-1205)
 Toronto 3421' (-1226)
 Lansing 3441' (-1246)
 Log T. D. 3667' (-1472)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 15 1964
 07-15-1964
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the TOWNS #1, SW SW NW Section 7-10S-18W, Rooks County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
 B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of July, 1964.

Leah Faye Hefke
 Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.