

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02424-00-00
Spot: NENESE Sec/Twnshp/Rge: 28-12S-17W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHMEIDLER WEST Well #: 2
County: ELLIS Total Vertical Depth: 3662 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3646	0	w/unknown sxs cmt
SURF	8.625	1341	0	w/unknown sxs cmt

\$ 119.02

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2007 1:00 PM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered 340 sxs 60/40 pozmix - 4% gel - 16 sxs gel spacer - 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2007 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:
Perfed at 1900' - 1350' - 775'.
Tied onto 5 1/2" - pumped 50 sxs cement with 100# hulls, followed with 16 sxs gel spacer and 300# hulls.
Pumped 330 sxs cement with 400# hulls - circulated cement out the backside - full.
Squeezed to Max. P.S.I. 600#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3646	3662		
3437			
3419			

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 10 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 9-18-07
INV. NO. 2008060415

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1588.
Plugged through: CSG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

SEP 05 2007

PPT

2008080808
12.5
P

28-12-17W
NE NE SE

Bay Newfoundland Co. #2 Schmeidler

Contr. Glen Peel Drilling Co. Ellis County

E 2128 Comm. 6-11-47 Comp. 8-29-47 IP 42 BOPD

Tops	Depth	Datum
Anh	1329	+799
LANS	3417	
ARB	3646	
T. D.	3662	

Casing
 8" 1349
 5" 3647
 Swb 1 1/2 BOPH/13 hrs
 Acid 500

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS
