


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-163-00661-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 9 Twp 10 Rge. 18 (X) W (W)
Location as "NE/CNW/SW" or footage from lines C, NW NW SE
Lease Owner E. K. Carey Contractor
Lease Name A. Garvart Well No. 1
Office Address Box 620, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 9-9-54 19
Application for plugging filed 9-8-54 19
Application for plugging approved 9-8-54 9:00 P.M. 19
Plugging commenced 9-9-54 9:00 P.M. 19
Plugging completed 9-9-54 11:15 P.M. 19
Reason for abandonment of well or producing formation Non Productive

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3841 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 200-155 feet to 40-8 feet for each plug set.

Circulate heavy mud on bottom, layed down half of drill pipe. Gunned pits circulated heavy mud, layed down all drill pipe but 8 joints. Ran measuring line to find fluid, filled to 200' with mud. Put plug there with 1/2 sack hulls and rock to hold weight of 8 joints drill pipe, mixed 15 sacks cement and put on that plug. Ran measuring line and filled with heavy mud to 40'. Put plug there with 1/2 sack hulls, mixed 10 sacks cement and filled to bottom of cellar floor.

09-13-1954

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. K. Carey Contractor
Address Box 620, McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Arland Bruce, Tool Pusher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Arland Bruce
Box 620 McPherson Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1954

[Signature]

My commission expires November 13, 1956

Notary Public.



24-2675-S 2-52-20M

E. K. Carey Contractor
 Box 620
 McPherson, Kansas

Elevations: 2190 K. B.

A. Garvart #1

C, NW NW SE
 Sec. 9-10-18W
 Rooks County, Kansas

Casing Record:
 8-5/8" @ 211' w/140 sks.
 Reg. bulk cement & 200# cc.

Well Commenced: 8-25-54
 Well Completed: 9-10-54 D & A

Contractor: E. K. Carey Contractor, Rig #1, Box 620, McPherson, Kansas
 Geologist: Don Hollar, E. K. Carey Drlg. Co., 815 Central Bldg. Wichita

Figures Indicate Bottom of Formation K. B.

Cellar	7	Geologist Tops:	
Clay	35	Topeka	3171
Sand	50	Heebner	3388
Shale	210	Toronto	3407
Shells	211	Lansing	3428
Shale and shells	675	Conglomerate	3670
Red shale and sand	1219	Simpson	3773
Shale and red bed, sandy	1295	Arbuckle	3795
Shale, shells and red bed	1565	Rotary Total Depth	3841
Shale	1580		
Anhydrite	1605		
Lime and shale	1880		
Shale and lime	2032		
Lime	2900		
Lime and shale	3025		
Shale and lime	3171		
Lime	3685		
Conglomerate	3765		
Shale, lime and chert	3795		
Lime	3841 TD		

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 11th day of September, 1954

09-13-1954
 E. K. CAREY CONTRACTOR

BY Herbert Rhoton
 Herbert Rhoton, Superintendent

John
 NP

My Commission Expires: November 13, 1956.

PLUGGING
 FILE SEC 9-10-18W R (16)
 BOOK PAGE 63 LINE 23