

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20186-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
03-27-1969

Operator's Full Name Adair Oil Company

Complete Address: Box 7011 Wichita, Kansas

Lease Name Meyers Well No. 1

Location N/2 SE SW Sec. 15 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3355'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Abercrombie Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 9:30P Day 24 Month 3 Year 1969

The Above well was plugged as follows:

RTD 3355' 8 5/8 csg set at 200' cwc 160 sk.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulld and 10 sk cmt to base  
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3/27/69  
INV. NO. 9520-U