

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20449-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1972
07-31-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company
Complete Address 217 N. Water Wichita, Kansas
Lease Name Charles Black Well No. 1-V
Location NE SE NW Sec. 15 Twp. 10 Rge. (E) (W) 18
County Rooks Total Depth 3760'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 4 A Day 30 Month 7 Year 1972

The above well was plugged as follows:

RTD 3760' 10 3/4 csg set at 200' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 8/1/72
INV. NO. 6090-W