

DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

15-163-01020-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 19 TWP. 10 RGE. 18

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-1 Lease Wise "A"

Operator Davis Bros Address 14E 3rd Tulsa, Okla

Field _____ County Rooks

Total Depth 3704 Feet.

Plugging Contractor Transit Corp

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 182' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 500', displaced 20 sax cement through drill pipe, heavy mud to 170', set cementing plug, 1/2 sack hulls and 15 sax cement, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

E. J. Kelly
District Conservation Agent

Date 12-23-57

RECEIVED
STATE CORP COM
DEC 27 1957

12-27-1957

PLUGGING
SEC 19 T 10 R 18 W
BOOK PAGE 72 LINE 20