

TO: -  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23317-00-00  
Spot: SW Sec/Twnshp/Rge: 3-14S-14W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: BOXBERGER H Well #: 14  
County: RUSSELL Total Vertical Depth: 3251 feet

Operator License No.: 7281  
Op Name: VONFELDT, ALAN J  
Address: 128 EVES DR  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3229	0	175 SX CMT
SURF	8.625	820	0	375 SX CMT

\$ 105.66

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2007 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID FUNK Company: VONFELDT, ALAN J. Phone: (785) 324-1041

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/28/2007 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2825'.  
Cut off casing at 1820'.  
Pulled to 1450' - pumped 130 sxs 60/40 pozmix - 4% gel w/300# hulls.  
Pulled to 850' - pumped 40 sxs cement with 100# hulls.  
Pulled to 150' - circulated with 55 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2980	2984		
2874	2880		

**INVOICED**  
DATE 9-18-07  
INV. NO. 2008060417

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 10 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMETING.

Plugged through: TBG

District: 04

*AD*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

*PST*

30020 (PCH) 10:21  
11/22/05

102:K01

ALAN VONFELDT  
RUSSELL KS 67665

3-14S-14W  
C SW/4

#H-14 BOXBERGER

site 1-1/4 S OF RUSSELL KS	co: RUSSELL	API 15-167-23317
contr: VONFELDT DRILLING #1	field HALL-GURNEY	
opd: BRAD HUTCHISON		
fr date 10/31/2005	spc date 11/22/2005	drig comp 11/30/2005
	card issued 02/06/2006	last revised 02/06/2006


E.L.V: 1828 KB, 1823 GL LOG	
tops.....	depth/datum
ANH.....	823 +1005
TOP.....	2694 -866
HEEB.....	2920 -1092
TOR.....	2939 -1111
LANS.....	2981 -1153
PBTD.....	3020 -1192
BKC.....	3234 -1406
GORHAM SD.....	3249 -1421
LTD.....	3249 -1421
RTD.....	3251 -1423

IP status  
OIL, P 20 BO & 200 BWP, SHAW 2874-2880 , LKC 2980-2984 , 01/24/2006  
NOTE: CORRECTION 11/28/2005 - ORIG FR IN C W/2 SW  
CSG: 8-5/8" 820 / 375 SX (ALT 1), 5-1/2" 3229 / 175 SX  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: LKC, GORHAM SD (OIL), PTD 3300 (GORHAM), MICT - CO, PB 3020, FF (TOP) 2874-2880 & (LKC) 2980-2984, W / 4 SPF, AC 3000 GAL (28% CRA), SWB LD, SO, SET 2-1/2" TBG AT 3000, NO PKR, POP, IPP 20 BO & 200 BWP, DOFP 1/24/2006, COMMINGLED - NO OTHER INFO AVAILABLE - TEMP COMP 2/6/2006

COPYRIGHT 2006  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS