

PR

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20413-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1972
CONSERVATION DIVISION
Wichita, Kansas
01-17-1972

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas 67202

Lease Name Dauwe Well No. 1

Location NE SE NE Sec. 29 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3720' 46.50

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling & Sons

Address Victoria, Kansas License No.

Operation Completed: Hour 1:30 A Day 10 Month 1 Year 1972

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set at 248' cwc 140 sk. Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Manning
Well Plugging Supervisor

DATE 1-18-72
INV. NO. 5024-W