

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20405-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
12-10-1971

Operator's Full Name Beacon Resources

Complete Address 1000 Century Plaza Wichita, Kansas

Lease Name Andreson Well No. 1

Location NE NW SE Sec. 29 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3285'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.       

Operation Completed: Hour 3:15 P Day 8 Month 12 Year 1971

The above well was plugged as follows:

RTD 3285' 8 5/8 csg set at 248' cwc 175 sk. Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 575' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/1/71  
INV. NO. 4804-W

Signed: [Signature]  
Well Plugging Supervisor