

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1967

08-14-1967

CONSERVATION DIVISION
Wichita, Kansas

15-163-20049-00-00

Operator's Full Name E. K. Edmiston

Complete Address: 425 First Natl. Bldg. Wichita, Kansas

Lease Name Sheppard Shepard ANH Well No. 1

Location NW NE NE Sec. 25 Twp. 10 Rge. 18 (E) (W) X

County Rooks Total Depth 3690

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 7:45 A Day 13 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3690' 8 5/8 csg set at 196' cwc 140 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 90 sc cem.
thru drill pipe. Heavy mud to 200' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/14/67

INV. NO. 6126-LW

Signed: Geo. J. Massey
Well Plugging Supervisor