

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20195-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
04-17-1969

Operator's Full Name Abercrombie Drilling Company

Complete Address: 801 Union Center Wichita, Kansas

Lease Name Schmidt Well No. X2 ANH KCC

Location SW NW SE Sec. 25 Twp. 10 Rge. (E) (W) 18

County Ellis Total Depth 3605

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor:      Co. Tools     

Address:      License No.     

Operation Completed: Hour 5:30P Day 5 Month 4 Year 1969

The Above well was plugged as follows:

RTD 3605' 8 5/8 csg set at 240' cwc 150 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Boyd Massey  
Well Plugging Supervisor

INVOICED

DATE 4/7/69

INV. NO. 9551-W