

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20407-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1971
CONSERVATION DIVISION
Wichita, Kansas
12-17-1971

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas

Lease Name Vine Well No. 1

Location 190' E & 75' S of NE SE SW Sec. 33 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3267'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling & Sons

Address Victoria, Kansas License No.

Operation Completed: Hour 4 P Day 14 Month 12 Year 1971

The above well was plugged as follows:

RTD 3267' 8 5/8 csg set at 242' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio F. Massey
Well Plugging Supervisor

DATE 12/17/71

INV. NO. 4833-W