

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 1103-20712-00-00

JAN 12 1979
01-12-1979
CONSERVATION DIVISION
Wichita, Kansas (Well 11)

Operator's Full Name Graves Drilling Co., Inc.
Complete Address 910 Union Center, Wichita, Ks. 67202
Lease Name Vine Well No. 1
Location NW NE SE Sec. 33 Twp. 10 Rge. (E) (W) 18
County Rooks Total Depth 3600'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Ks. 67524 License No. 683
Operation Completed: Hour 12:40 P Day 11 Month 1 Year 1979

The above well was plugged as follows:

Total Depth 3600' 8 5/8 csg set 234' cwc 160 sk.
5 1/2 csg set 3597' cw 150 sk cem.
Filled 5 1/2 csg W/sd (3600'-3575') dumped 4 sk cem W/dump bailer. (3575'-3545')
Cutoff & recovered 2627' of 5 1/2 csg.
Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls -followed
with 70 sk 50-50 poz 6% -displaced with 8 sk gel & water -released cementing
plug & capped with 70 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-15-79
NO. 8943-W

Signed: [Signature]
Well Plugging Supervisor