

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 163-21, 293-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name PETROLEUM ENERGY, INC.

Complete Address 710 ONE TWENTY BLDG. - WICHITA, KANS.

Lease Name BEAVER Well No. #1

Location SW-SW-SW Sec. 32 Twp. 10^S Rge. 18^W (East) (West)

County ROOFS. Total Depth 2542^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor WHITE & ELLIS DRILLING, INC.

Address BOX 448 ELDORADO, KANS. License No. _____

Operation Completed: Hour: 8:50^{AM} Day: 22ND Month: APRIL Year: 19 81

The above well was plugged as follows:

8 5/8" 220 FE SR CUC w/ 165ST COMMON - 2% GEL. 3% CMC.
ORDERED 110ST 50/50 Pozmix 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 720 FE w/ 65ST CNT.

2ND PLUG @ 240 FE w/ 30ST CNT.

3RD PLUG -> SOLID BRIDGE @ 40 FE w/ 10ST CNT.

5ST IN RAT HOLE.

CEMENTED BY SUN CNT.

APR 24 1981
04-24-1981

I hereby certify that the above well was plugged as herein stated.

VOICED
5-29-81
5552-W

Signed: [Signature]
Conservation Division Agent