

6 050175

API NUMBER 15-16322637-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE. 7/8 - 1/4, SEC. 11, T. 10 S, R. 18 W

1700 feet from S section line
3180 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9730
Operator: The Merlin Corp.
Name & Address: 509 Union Center
Wichita Kans 67202

Lease Name Malin Well # 1-11
County Rooks
Well Total Depth 3819 12 1/2 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 24 7/8

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor: Murfin Drilling Co. License Number 6033
Address: 617 Union Center Bldg - Wichita Kans 67202

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Albert Augustine
(company name) Murfin Drilling Co. (phone) _____

Order 205 spx 50/50 Poz mix 670 gal 370 cc - 1 sac flocc - 1 sac hulls @ 8 5/8 Plug

Get Pitts circulate hole with heavy mud - with heavy mud between all
Plugs - good circulation - no fluid loss - Set 1st Plug at 3760' w/ 20 spx cement.
2nd plug 1550' w/ 25 spx - 3rd plug @ 920' w/ 100 spx and 1 sac flocc - 4th Plug @
260' w/ 40 spx - 5th plug @ 40' - 8 5/8 Plug 1 sac hulls @ 10 spx - 10 spx in rat hole

Plugging Proposal Received by Gilbert P. Leiker
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 PM Day: 26 Month: Feb Year: 1985

ACTUAL PLUGGING REPORT

1st Plug @ 3760 w/ 20 spx
2nd Plug @ 1550 w/ 25 spx
3rd Plug @ 920' w/ 100 sp 1 sac flocc
4th Plug @ 260' w/ 40 spx
5th Plug @ 40' w/ 8 5/8 Plug 1 sac hulls @ 10 spx cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 04 1985
03-04-1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: 10 spx in rat hole - By Allied cementing Co.
(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

Witnessed by Marion Schmidt 3-7-85
DATE

Signed Gilbert P. Leiker
(TECHNICIAN) 2-28-85

INV. NO. 7254 MAR 26 1985