

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 (of this well)

04-11-1978  
RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Tenneco Oil Co.  
Complete Address Suite 139, Ciudad Bldg., 3000 United Founders Blvd., Oklahoma City Oklahoma 73112

Lease Name Williams Field Waterflood Unit Well No. 2-2

Location SE NW SW Sec. 9 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3764

Abandoned Oil Well X Gas Well KCCOB Input Well 200 SWD Well D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 2 P Day 7 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 3764' 8 5/8 csg set 1593' cwc

5 1/2 csg 3575' cw 150 sk.

5 1/2 csg PBTD 3650' and perf. (3565')

Filled 5 1/2 csg W/sd (3650'-3434') dumped 4 sk cem W/dump bailer. (3434'-3400')

Cutoff & recovered App. 2200' of 5 1/2 csg.

Drl. mud to 575' -set rock & sand bridge (575'-560')

Filled with readymix cem. 560' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 4-11-78

INV. NO. 7096.0

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED