



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 29 1963
 01-29-1963
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Allen Fender of Fender Pipe & Supply has this

date requested permission to plug the following described well:

Mr. Fender guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply

Complete Address: Box 302 Russell, Kansas

Lease Name: Hilger Well No. 1

Location: NW NW NE Sec. 5 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3740 Oil Well x

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fender was instructed to plug the well as follows:

Sand back to 3430', set 5 sax cement with dump bailer
Pull pipe to 550', circulate hole with heavy mud, set 20 sax cement
through 5 1/2" at 550', heavy mud to 180', displace 20 sax cement
through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Very truly yours,

Edwin Little
 Conservation Division Agent