



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

15-163-60918-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1959
 05-13-1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 5-8-59, 19 , authorized the following plugging operation:

Operator's Full Name: Rex & Morris

Complete Address: Box 334 El Dorado, Kans

Lease Name: Williams Well No. 1

Location: CNW SE Sec. 5 Twp. 10 Rge. 18 (E) (W)

County: Rooks Total Depth: 3828

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

8 5/8" at 213' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 600', displaced
20 sax cement through drill pipe, heavy mud to 180', set cementing plug
and displaced 15 sax cement through drill pipe, heavy mud to 40', set
cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Very truly yours,

Signed: *Jewel M. Ogden*
 Conservation Division Agent