



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-163-20186-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 27 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 03-27-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Adair Oil Co.

Complete Address: Wichita, Ks.

Lease Name: Meyers Well No. 1

Location: N/2 SE SW Sec. 15 Twp. 10 Rge. (E)(W) 18

County: Rooks Total Depth 3355 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cement thru drillpipe. Heavy mud to 180' set cementing plug and
displace 20 sk cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cement to base of cellar. Plug rat hole
with 2 sk cement.

Very truly yours,

Boo J. Marney
 Conservation Division Agent