



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-163-20388-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

08-23-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Hunt of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Court, 220 W. Douglas Wichita, Ks.

Lease Name: Vohs Well No. 1

Location: SE SE SE Sec. 18 Twp. 10 Rge. (E)(W) 18

County: Rooks Total Depth 3763' Oil Well

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Hunt was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 680' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Musary  
Conservation Division Agent