

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02423-00-00
Spot: NWNESE Sec/Twnshp/Rge: 28-12S-17W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: SCHMEIDLER WEST Well #: 1
County: ELLIS Total Vertical Depth: 3674 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3669	0	w/unknown sxs cmt
SURF	8.625	1344	0	w/unknown sxs cmt

\$ 119.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2007 8:00 AM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 800# hulls.
Perf at 1900' - 1375' - 800'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2007 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RT in to 1872' - pumped 130 sxs cement with 400# hulls.
PTO to 934' - pumped 55 sxs cement with 100# hulls - good circulation of cement.
PTO tied onto the 5 1/2" - squeezed with 25 sxs cement.
Max. P.S.I. 400#. S.I.P 350#.
Tied onto backside - squeezed with 5 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3669	3674		
3550	3566		
3529			
3470			
3437			
3419			

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 10 2007

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 9-18-07

INV. NO. 2008060415

Remarks: QUALITY OIL WELL CEMENTING-TICKET #1589.

Plugged through: TBG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

PCT

2002-6012
10 9 10

BAY PETROLEUM CORP. #1 SCHEIDLER 28-12-17W
NW NE SE
Contr. ELLIS County

E 2136 Comm. 3-11-15 Comp. 6-8-15 IP 25 ROPD

Tops	Depth	Datum	Casing
ANHY	1337	+799	8" 1344 5" 3669
TOP	2103		
LANS	3129		
SIMP	3650		
ARB	3667		
TD	3674		

SSO 3493-3529
300' OIH/12 hrs @ 3674
Butane 1000; A/500

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS