

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
05-13-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-01857-00-00

Operator's Full Name Murfin Drilling Company

Complete Address: 617 Union Center Wichita, Kansas

Lease Name Sheppard "A" Well No. 1

Location NE NE SE Sec. 14 Twp. 10 Rge. 18 (E) (W) X

County Rooks Total Depth 3780'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Russ Casing Pulling

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 1:30<sup>30</sup>P Day 6 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3780' 8 5/8 csg set at 246' cwc/ Cem. Mat. 150 sc 50-50 poz W/6% gel.

5 1/2 csg set at 3625' cw 150 sc cement.

Top Perf. 3400' Filled with sand to 3300' and dumped 5 sc cement with dump bailer/

Recov. 2000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 30 sc gel W/10 sc hulls, plug and 150 sc

50-50 poz cement W/6% total gel. (225 Cu. Ft.)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 5/15/68  
INV. NO. 7758-4