

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-163-20078-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1967
12-04-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Three G Oil, Inc.,

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name Benedick Well No. 1

Location SW NE SW Sec. 3 Twp. 10 Rge. 18 (E) (W) X

County Rooks Total Depth 3770

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: H - 30 Drlg, Inc.,

Address: Wichita, Kansas License No.

Operation Completed: Hour 6 A Day 2 Month 12 Year 1967

The Above well was plugged as follows:

RTD 3770' 8 5/8 csg set at 239' cwc. 180 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc

cement thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cem.

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to

base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 12/5/67
INV. NO. 6841-W



15-163-20078-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-163-20078-00-00

RECEIVED
 CONSERVATION DIVISION
 DEC 4 1967
 12-04-1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.,

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name: Benedick Well No. 1

Location: SW NE SW Sec. 3 Twp. 10 Rge. 18 (E)(W) X

County: Rooks Total Depth 3770 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 800' and displace
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
 Conservation Division Agent