

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
04-28-1961
APR 23 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-01121-00-01

File No. _____ County: _____ Rooks _____
Location: NW NW NE Sec. 3 Twp. 10 Rge. 18 (E) (W) _____
Name of Field: _____ Total Depth: 3729

I have this date completed supervision of plugging of:

Lease Name: Bright Well No. 1
Operator's Full Name: J. O. Farmer Inc
Complete Address: Russell, Kansas
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kansas License No. 49
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 25 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 236' circulated with cement - 5 1/2" 3729' with 100 sax cement
PB 3630', perforated 3683-3557-3530' - filled with sand to 3500', set
5 sax cement with dump bailer, pulled 1012' 5 1/2" to 500', circulated hole
with heavy mud through 5 1/2" at 500', (26 sax Gel), displaced 20 sax
cement through 5 1/2" at 500', heavy mud to 160', displaced 20 sax cement
through 5 1/2" at 160', heavy mud to 30', set bridge and 10 sax cement to 0'.
Mudding and cementing by Globe Cementing Co.

Signed: *Edwin Petty*
Conservation Division Agent

Reviewed: *Harold Shelle*
Field Supervisor

Remarks:

INVOICED
DATE 5/4/61
INV. NO. 3016-W