

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-163-00894-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 108-1

LOCATION SE SW SE

SEC. 5 TWP. 10 RGE. 18W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Williams

Operator K & E Drg Co Inc. Address 719 Union Center Wichita,

Field _____ County Rooks

Total Depth 3466 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 204' circulated with cement - 4 1/2" at 3462' with 75 sax
cement behind - perforated at 3394'.

Filled with sand to 3380', set 3 sax cement with dump bailer,
pulled 2770' 4 1/2" - mud to 210', set rock and 15 sax cement, mud
to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
SEC. 5 T. 10 R. 18W
BOOK 108 PAGE 28 LINE 1

E. H. ...
District Conservation Agent
12-1-56
DATE
RECEIVED
DEC 10 1956
12-10-1956
CONSERVATION DIVISION
WICHITA, KANSAS