

15-163-00918-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1959
05-13-1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____
Location: CNW SE Sec. 5 Twp. 10 Rge. 18 (E) (W) _____
Name of Field: _____ Total Depth: 3828

I have this date completed supervision of plugging of:
Lease Name: Williams Well No. 1
Operator's Full Name: Rex & Morris
Complete Address: Box 334 El Dorado, Kans
Plugging Contractor: same
Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 11:30 Day 8 Month 5 Year 59

The above well was plugged as follows:
8 5/8" at 213' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 600', displaced 20
sax cement through drill pipe, heavy mud to 180', displaced 15 sax cement
through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls
and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 5 T. 10 R. 18W
BOOK PAGE 42 LINE 12