

15-163-00673-00-01

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 72-13

LOCATION SE SE SE

SEC. 5 TWP. 10 RGE. 18

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Williams

Operator K & E Drg ~~Co~~ INC Address Wichita, Kans

Field _____ County Rooks

Total Depth 3773 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 4 1/2" at 3770', with

150 sax cement behind. perforate at 3385'.

Set plugs at 3350', sand and 4 sax cement set with dump bailer,

pulled 1800' 4 1/2" - pumped hole full mud, set cementing plug at 160',

rock and 15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

District Conservation Agent

Date 7-6-56

07-07-1956
DIVISION
Kansas

PLUGGING
FILE SEC 5 T. 10 R. 18W
BOOK PAGE 12 LINE 13