

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00896-00-01

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1963
01-29-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Fender Pipe & Supply Co
Complete Address: Box 302 Russell, Kansas
Lease Name Hilger Well No. 1
Location NW NW NE Sec. 5 Twp. 10 Rge. (E) (W) 18
County Rooks Total Depth 3740
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons
Address: Russell, Kansas License No.
Operation Completed: Hour 5PM Day 24 Month 1 Year 63

The Above well was plugged as follows:

8 5/8" 210' circulated with cement - 5 1/2" 3740' with 100 sax cement.
Perforated 3441'

Filled with sand to 3430', set 5 sax cement with dump bailer, pulled 3130'
5 1/2" to 570', circulated hole with heavy mud through 5 1/2" (26 sax Gel),
displaced 20 sax cement through 5 3/8" at 570', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/29/63
INV. NO. 6486-W

Signed: Edon Lacey
Well Plugging Supervisor