

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00750-00-00

File No. 120-44 County: Rooks

Location: SW NW SW Sec. 5 Twp. 10 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: ~~5829~~ 5829

I have this date completed supervision of plugging of:

Lease Name: Gilbert Well No. 1

Operator's Full Name: Davis Bros

Complete Address: 14 E 3rd R Tulsa, Okla

Plugging Contractor: Barnes & Sons Pipe Pulling

Address: Russell, Kans License No. 9

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 14 Month 8 Year 58

The above well was plugged as follows:

8 5/8" at 180' circulated with cement. 4 1/2" 5817' with 175 sax
cement behind - perforated 5000'.

Filled with sand to 5590', set 3 sax cement with dump bailer, pulled
5018' 4 1/2" to 550', circulated hole with heavy mud (30 sax Gel),
displaced 20 sax cement through 4 1/2" at 550', heavy mud to 180',
displaced 20 sax cement through 4 1/2" at 180', heavy mud to 35', set
rock and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 5 T 10 R 18W
BOOK PAGE 120 LINE 44

AUG 19 1958
08-19-1958
CONSERVATION DIVISION
Wichita, Kansas