

15-163-00629-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1959
05-11-1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 33-37 County: _____ Rooks
Location: CN 1/2 NE NW Sec. 6 Twp. 10 Rge. 18 (E) (W) X
Name of Field: _____ Total Depth: 3760

I have this date completed supervision of plugging of:

Lease Name: Williams Well No. 1
Operator's Full Name: R. A. Comeau
Complete Address: c/o West Supply Co Box 327 Chase, Kans
Plugging Contractor: West Supply Co
Address: Chase, Kans License No. 14

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 6 Month 5 Year 59

The above well was plugged as follows:

8 5/8" at 160' circulated with cement - 5 1/2" 3483' cemented.
PB. to 3465' - perforated 3410' - filled with sand to 3400', set 4 sax cement
with dump bailer - pulled 3146' 5 1/2" to 550', circulated hole with heavy mud
through 5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', heavy mud
(Gel)
to 150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.
Mudding and cementing by West Supply Co's pump truck.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 6 T. 10 R. 18W
BOOK PAGE 33 LINE 39