

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

ANH ~~xxx~~
163
API Number 15 - ~~167~~ - 20,858-00-00 (of this well)

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Jones Well No. 1

Location SE SW NE Sec. 10 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Big Springs Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 8:15 P Day 9 Month 12 Year 1978

The above well was plugged as follows:

RTD 3450' 8 5/8 csg set 214' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 12-13-78
INV. NO. 8734-W