

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 14 Twp. 10 Rge. 18 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner C-G Drilling Co.

Lease Name Finnesy Well No. 1

Office Address 544 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 18 1953

Application for plugging filed 12-18 1953

Application for plugging approved 12-18 1953

Plugging commenced 12-18 1953

Plugging completed 12-18 1953

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3816 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	184.62	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 180'; set solid plug: 1/2 sack hulls, 15 sacks cement. Filled hole with mud to 40'; set plug then filled to top with 10 sacks cement, 1/2 sack hulls.

Rec'd  
12-24-1953

Name of Plugging Contractor C-G DRILLING CO.  
Address 544 Petroleum Bldg., Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Vicky Jacobs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) Vicky Jacobs  
544 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1953

Barbara Sanderson  
Notary Public.

My commission expires 6/17/57



15-163-00556-00-00

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. FARM NAME Finnesy No. 1  
 LOCATION NE NE NE Section 14-10S-18W  
 POOL NAME Wildcat COUNTY Rooks STATE Kansas  
 COMMENCEMENT DATE December 9, 1953 COMPLETION DATE December 18, 1953

LOG OF WELL

Elevation: 2186 R.B.  
 All measurements from the top of rotary bushing.


FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	185	Sand-Shale		
185	575	Shale-Shells-Sand		
575	1050	Shale-Shells		
1050	1270	Sand		
1270	1355	Shale-Shells		
1355	1425	Shale		
1425	1568	Red Bed	0° - 1500'	
1568	1606	Anhydrite		
1606	1675	Shale		
1675	2030	Shale	0° - 2000'	
2030	2220	Shale-Shells		
2220	2420	Lime-Shale		
2420	2515	Shale-Lime		
2515	2695	Lime-Shale		
2695	2790	Lime-Shale		
2790	2890	Lime-Shale		
2890	3000	Lime-Shale	0° - 3000'	
3000	3100	Lime-Shale		
3100	3194	Lime-Shale		
3194	3280	Lime-Shale		
3280	3338	Lime-Shale		
3338	3395	Lime-Shale		
3395	3442	Lime		DST 3434-3442
3442	3487	Lime		
3487	3540	Lime-Shale	0° - 3500'	
3540	3580	Lime-Shale		DST 3572-3580
3580	3589	Lime		
3589	3660	Lime-Shale		
3660	3730	Lime-Shale		
3730	3755	Lime-Shale		
3755	3816	Lime-Shale		
3816	3816	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 184.62' (6 jts) 8-5/8" Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK ) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.



C-G DRILLING CO.

By Wicky Jacobs  
 Ofc Mgr.

Subscribed and sworn to before me this 23rd day of December, 1953.

My commission expires: 6/17/57

Barbara Donaldson  
 Notary Public