

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Coalbed Technology, L.L.C.
Address: 401 S. Boston, Ste 3000, Tulsa, OK 74103
Phone: (918) 747-7771 Operator License #: 33564
Type of Well: gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/1/07 (Date)
by: Steve Korf (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cherokee Depth to Top: 228 Bottom: 243 T.D. 661
Cherokee Depth to Top: 610 Bottom: 614 T.D. 661
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 011-22922-00-00
Lease Name: McVay
Well Number: 1-26
Spot Location (QQQQ): SW - NE - NW - NW
440 Feet from North / South Section Line
820 Feet from East / West Section Line
Sec. 26 Twp. 26 S. R. 22 East West
County: Bourbon *KCC PKT 9/12/07*
Date Well Completed: 10/01/07 *pu*
Plugging Commenced: 03/12/07 *RBDMS*
Plugging Completed: 08/08/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherokee Coal 228-243	gas	0	24	8 5/8	24	3
Cherokee 610-614	gas	0	661	4 1/2	661	3

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tie onto 4 1/2 csg. Pump 182 sx cmt. Shut well in & WOC. Used cotton seed hulls in first 50 sx. Run 1" & tag cmt @ 275. Pump 28 sx cmt from 275' & circulate to surface. Pull 1" and top off from surface. Cut off casing strings 3' below GL. Restore Location.

Name of Plugging Contractor: Willis Well Service License #: 33798
Address: P.O. Box 142, Chanute KS 66720
Name of Party Responsible for Plugging Fees: Coalbed Technology, LLC
State of Oklahoma County, Tulsa, ss.
Bruce Galbierz, Partner/Engineer

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct so help me God.

MARY M. ROBLES
NOTARY PUBLIC - STATE OF OKLAHOMA
TULSA COUNTY
COMMISSION # 99016071
RECEIVED

(Signature) Bruce Galbierz
(Address) 401 S. Boston, Ste 3000, Tulsa, OK 74103
SUBSCRIBED and SWORN TO before me this 28th day of August, 20 07
Mary M. Robles My Commission Expires: 11.06.07
Notary Public

AUG 31 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA KS

PKT