


15-163-21138-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rocks _____ County. Sec. 3 Twp. 10S Rge. 18 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
NW SE SW
Lease Owner K & E Petroleum, Inc.
Lease Name KRAYBILL Well No. 1
Office Address 816 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed 08-27 19 80
Application for plugging filed 08-27 19 80
Application for plugging approved 08-27 19 80
Plugging commenced 08-27 19 80
Plugging completed 08-27 19 80
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas available
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT


Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3775'.
Set 1st plug @ 800' with 70 sx.
2nd plug @ 270' with 25 sx.
3rd plug @ 40' solid bridge with 10 sx.
rathole with 5 sx., 50/50 posmix, 6% gel.

Plug was down @ 9:00 p.m. 08-27-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.



STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 1980

My commission expires 08-18-84

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.



CONTRACTOR'S WELL LOG

15-163-21138-00

OPERATOR: K & E Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KRAYBILL #1
 LOCATION: NW SE SW, Section 3-10S-18W
 Rooks County, Kansas
 SPUD DATE: 08-21-80
 COMPLETION DATE: 08-27-80

0	1519	Sand & Shale
1519	1555	Anhydrite
1555	1803	Sand & Shale
1803	3775	Shale & Lime
	3775	Rotary Total Depth

Spud hole @ 4:00 p.m. 08-21-80. Cut 283' of a 12-1/4" hole. Ran 7 joints of new 20# 8-5/8" casing (tally 273.01') Set @ 279.51' with 180 sx. of common, 2% gel, 3% c.c. Plug was down @ 10:00 p.m. 08-21-80. Cement did circulate.

T.D. 3775'. Set 1st plug @ 800' with 70 sx., 2nd plug @ 270' with 25 sx., 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 6% gel. Plug was down @ 9:00 p.m. 08-27-80.

SAMPLE TOPS:

Anhydrite 1519'
 B/Anhydrite 1555'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP - 8 1980
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KRAYBILL #1, NW SE SW, Section 3-10S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of September, 1980.

Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public

