


15-163-20078-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 3 Twp. 10S Rge. (E) 18 (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines NW SE SW SW NE SW
Lease Owner Three G Oil, Inc. SW NE SW
Lease Name Benedick Well No. 1
Office Address 1101 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 2 1967
Application for plugging filed Verbal Authority 1967
Application for plugging approved Verbal Authority 1967
Plugging commenced December 2 1967
Plugging completed December 2 1967
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 239' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,770 feet (rotary total depth) to 800 feet. Set plug at 800 feet and cemented by Halliburton Pump Truck with 100 sacks cement. Filled hole with heavy rotary mud to 240 feet. Set plug at 240 feet and cemented by Halliburton Pump Truck with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented by Halliburton Pump Truck with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1967
12-07-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main St., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 North Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1967

My commission expires April 21, 1971
Martha Hartpence
Notary Public.

15-163-20078-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Three G Oil, Inc.

SEC. 3 T. 10S R. 18W

FARM Benedick


NO. 1

LOC. ~~NWSE~~ SW
SW NE SW

COUNTY Rooks

TOTAL DEPTH 3,770'
COMM. November 18, 1967
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COMP. December 2, 1967



RECEIVED
DEC 7 1967
CORRELATION DIVISION
Wichita, Kansas

CASING

20 10
15 8 -5/8" 239' cemented w/185 sx cement ELEVATION 2,175 KB
12 6
13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

ELECTRIC LOG TOPS

| | | | | |
|---------------------|-------|------------------|-------|---------|
| Surface Clay & Sand | 100 | | | |
| Shale | 1,040 | Anhydrite | 1,522 | + 653 |
| Sand | 1,130 | Base Anhydrite | 1,556 | + 619 |
| Shale & Shells | 1,480 | Topeka | 3,131 | - 956 |
| Shale | 1,534 | Heebner | 3,345 | - 1,170 |
| Anhydrite | 1,569 | Toronto | 3,367 | - 1,192 |
| Red Bed | 1,870 | Lansing | 3,390 | - 1,215 |
| Shale | 2,080 | Base K. C. | 3,612 | - 1,437 |
| Lime & Shale | 2,300 | Conglomerate | 3,642 | - 1,467 |
| Lime | 2,490 | Simpson Shale | 3,710 | - 1,535 |
| Lime & Shale | 2,730 | Simpson Dolomite | 3,722 | - 1,547 |
| Shale & Lime | 3,152 | Arbuckle | 3,744 | - 1,569 |
| Lime | 3,660 | Log T. D. | 3,765 | - 1,590 |
| Conglomerate | 3,732 | Rotary T. D. | 3,770 | - 1,595 |
| Lime | 3,770 | | | |
| Rotary Total Depth | 3,770 | | | |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 6th day of December, 1967.

Martha Hartpence
Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971