

15-163-01121-00.06

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above
Section Plat

Rooks County. Sec. 3 Twp. 10 Rge. 18 (W)
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW, NW, NE. 330' E. 330' W.
 Lease Owner Lafayette Oil Company. 125 W. 3rd. Tulsa 3, Okla.
 Lease Name Bright Well No. 1
 Office Address 125 W. 3rd. Tulsa 3, Oklahoma.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 4, 1953 19
 Application for plugging filed April 4, 1953 19
 Application for plugging approved April 4, 1953 19
 Plugging commenced April 4, 1953 19
 Plugging completed April 4, 1953 19
 Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays Kansas
 Producing formation Depth to top Bottom Total Depth of Well 3732' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale & shells				8 5/8"	236'	None
This 8 5/8" casing was cemented with 150 sacks of cement. The cement circulated.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This well filled from 3732' up to 220' with heavy mud. Set Halliburton plug at 220'.
 Dumped 1/2 sack of hulls on top of plug, then dumped 15 sacks of cement on top of hulls.
 Filled hole from top of cement up to 40' with heavy mud.
 Set Halliburton plug at 40' dumped 1/2 sack of hulls on top of plug, Dumped 10 sacks of cement on top of hulls, This filled the hole up in the cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 04-18-1953
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
 Address

STATE OF Kansas, COUNTY OF Barton, ss.
 James R. Pryor (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Pryor
 (Address)

SUBSCRIBED AND SWORN to before me this 17 day of April, 1953
 Isabella Beuker
 Notary Public.

My commission expires Oct. 17, 1955

PLUGGING
 FILE SEC 3 T 10 R 18 W
 BOOK PAGE 90 LINE 17

BRIGHT #1

15-163-01121-00-00

NW/4 NW/4 NE/4 pf Section 3-10S-18W Rooks County, Kansas

Rigged up Rotary Tools 3/22/53
Tore down Rotary Tools 4/4/53

Run 6 Jts (240') of 8 5/8" Lap-Weld
Surface pipe set at 236'. Cemented
with 150 sacks cement, 2 sacks Cal.
Cl.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand, shale & shells	0'	183'
Shale & shells	183	236
Shale, shells, redbed & sand	236	913
Shale & sand	913	1288
Anhydrite	1288	1320
Shale & shells	1320	1351
Shale & lime streaks	1351	1757
Shale & lime & iron	1757	2110
Shale & shells	2110	2420
Lime & shale	2420	3030
Shale, lime & sand streaks	3030	3123
Lime & shale	3123	3230
Lime	3230	3279
Lime & shale	3279	3330
Lime	3330	3348
Lime & chert	3348	3383
Lime	3383	3515
Shale & lime streaks	3515	3570
Lime, shale & chert streaks	3570	3640
Lime & shale	3640	3660
Conglomerate	3660	3718
Arbuckle	3718	3732 TD

I, June Swaney, do hereby certify that the foregoing log is true and correct,
to the best of my knowledge and belief.

Subscribed and sworn to before me this 6th day of April, 1953.

My commission expires: January 30, 1957

PLUGGING
 FILE SEC 3 T10 R 18W
 BOOK PAGE 80 LINE 17